Concord-Carlisle Regional High School



omrarchitects

Agenda

OPM Update

Process Review

Review Preferred Alternatives

Evaluation Matrices

OPM Update

Concord-Carlisle High School Revitalization - Comparative Options Value Analysis

April 2011
April 29, 2012 (revised - after further consideration regarding schedule, option 3 was updated to indicate a estimated schedule of 42 months.)

	No-Build		Reno	vation/Addition Options			New Construction Options						
	Option 1	Option 2	Option 3	Option 4	Option 5	Option 6	Option 7	Option 8	Option 9A	Option 9B	Option 10		
	Code upgrade Multi phase Proj	Full Renovation Multi phase Proj	40	Ren/Addition Multi phase Proj	Ren/Addition Multi phase Proj	Ren/Addition Multi phase Proj	Multiple Bldgs Multiple Phases	Multiple Bldgs Multiple Phases	Single Bldg Dbl Ph w/ mods	Single Bldg Dbl Ph w/o mods	Single Bldg Single Phase		
Anticipated construction duration	38	42	42	46	41	44	48	48	34	48	32		
Square Footage	233,800	248,000		248,000	248,000	248,000	248,000	248,000	248,000	248,000	248,000		
Cost per SF based on Building Construction (line 2)	\$147	\$203	months	\$220	\$217	\$220	\$222	\$222	\$218	\$218	\$218		
Cost per SF based on Total Project Cost (line 19)	\$299	\$369	months	\$396	\$384	\$394	\$399	\$402	\$373	\$391	\$367		
1 Hard Costs													
2 Building construction (a)	\$34,297,500	\$50,303,100	\$51,583,550	\$54,485,900	\$53,754,000	\$54,494,000	\$55,111,600	\$54,991,400	\$53,947,440	\$53,947,440	\$54,073,860		
3 CM/GC PR/GC - mgmt during constr (b)	\$7,980,000	\$8,820,000	\$8,820,000	\$9,660,000	\$8,610,000	\$9,240,000	\$10,080,000	\$10,080,000	\$7,140,000	\$10,080,000	\$6,720,000		
4 CM/GC Fee (2%)	\$845,550	\$1,182,462	\$1,208,071	\$1,282,918	\$1,247,280	\$1,274,680	\$1,303,832	\$1,301,428	\$1,221,749	\$1,280,549	\$1,215,877		
4 Asbestos abatement	\$1,300,000 (c)	\$1,300,000 (c)	\$1,300,000 (c)	\$1,200,000 (c)	\$1,200,000 (c)	\$1,200,000 (c)	\$1,200,000 (c)	\$1,200,000 (c)	\$1,000,000	\$1,000,000	\$1,000,000		
5 Building take downs			\$377,300 \$7/sf	\$1,058,400 \$7/sf	\$1,124,200 \$7/sf	\$1,302,700 \$7/sf	\$1,636,600 \$7/sf	\$1.636.600 \$7/sf	\$1,402,800 \$6/sf	\$1,402,800 \$6/sf	\$1,402,800 \$6		
6 Site improvements (a) (d)	\$2,000,000	\$2,000,000	\$2,000,000	\$2,500,000	\$2,500,000	\$2,500,000	\$4,000,000	\$4,000,000	\$5,000,000	\$5,000,000	\$5,000,000		
7 Escalation	\$1,856,922 4%	\$2,862,250 4.5%	\$2,611,557 4%	\$3,509,361 5%	\$3,079,597 4.5%	\$3,500,569 5%	\$2,933,281 4% \$3,813,266 5%	\$3,660,471 5% \$3,843,495 5%	\$2,788,480 4% \$3,625,023 5%	\$3,635,539 5% \$3,817,316 5%	\$2,776,501 4% \$3,609,452 5%		
8 Hard contingency (e)	\$4,827,997 10%	\$6,646,781 10%	\$6,790,048 10%	\$5,527,243 7.5%	\$5,363,631 7.5%	\$5,513,396 7.5%							
9 Soft Costs													
10 Design costs (f)	\$4,186,478	\$5,386,876	\$5,481,432	\$5,753,429	\$5,612,722	\$5,741,521	\$5,804,715	\$5,842,804	\$5,567,530	\$5,809,819	\$5,547,909		
11 A/E CA mgmt (g)	\$2,280,000 60k/m	\$2,100,000 50k/m	\$2,520,000 60k/m	\$2,300,000 50k/m	\$2,050,000 50k/m	\$2,200,000 50k/m	\$2,400,000 50k/m	\$2,400,000 50k/m	\$2,040,000 60k/m	\$2,400,000 50k/m	\$1,920,000 60		
12 OPM CA mgmt (h)	\$1,900,000	\$2,100,000	\$2,100,000	\$2,300,000	\$2,050,000	\$2,200,000	\$2,400,000	\$2,400,000	\$1,700,000	\$2,400,000	\$1,600,000		
13 FFE / technology (\$3,200/student)	\$4,120,000 (c)	\$4,120,000 (c)	\$4,120,000 (c)	\$4,120,000 (c)	\$4,120,000 (c)	\$4,120,000 (c)	\$4,120,000 (c)	\$4,120,000 (c)	\$3,920,000	\$3,920,000	\$3,920,000		
14 Temp parking / road access logistics	\$100,000	\$200,000	\$200,000	\$200,000	\$200,000	\$250,000	\$400,000	\$400,000	\$400,000	\$400,000	\$400,000		
15 Temp modulars / storage	\$2,219,500	\$2,319,500	\$2,169,500	\$2,219,500	\$2,119,500	\$2,069,500	\$1,668,700	\$1,668,700	\$930,700	14.5	2		
16 Relocation / moving expenses	\$500,000	\$500,000	\$400,000	\$350,000	\$350,000	\$350,000	\$300,000	\$300,000	\$250,000	\$250,000	\$250,000		
Misc expenses (testing, legal, utility B/C, other)	\$700,000	\$900,000	\$900,000	\$900,000	\$900,000	\$900,000	\$900,000	\$900,000	\$900,000	\$900,000	\$900,000		
18 Soft contingency (5%)	\$800,299 5%	\$881,319 5%	\$894,547 5%	\$907,146 5%	\$870,111 5%	\$891,551 5%	\$899,671 5%	\$901,575 5%	\$785,411 5%	\$803,991 5%	\$726,895 59		
19 Comparative Values	\$69,914,246	\$91,622,288		\$98,273,898	\$95,151,041	\$97,747,917	\$98,971,664	\$99,646,473	\$92,619,133	\$97,047,454	\$91,063,296		
20 % above(below) new construction - option 10	-23%	1%	93.5	8%	4%	7%	9%	9%	2%	7%			
21 % of total project value compared to total hard costs value	76%	80%	30.0	81%	81%	81%	81%	81%	82%	83%	83%		
22 % of total project value compared to total soft costs value	24%	20%	million	19%	19%	19%	19%	19%	18%	17%	17%		

(a) Disposal of contaminated soil is EXCLUDED. Unknown at this time.

(b) Value of \$210,000 carried per month. Length of schedule is the cost driver.

(c) Premium for multiple mobilizations.

(d) In depth cost analysis has not been performed.

(e) 10% carried for renovation, 5% for new, 7.5% for hybrids.

(f) 6% is carried based on total hard construction costs + 1,000,000 for feasibility and schematic. Excludes CA costs, carried in line 11.

(g) Based on \$60,000 or \$50,000 per month. Length of schedule is the cost driver.


(h) Based on \$50,000 per month. Length of schedule is the cost driver.

Disclaimer

These values are not to be considered as a project budget. This analysis was utilized to compare various options to one another to determine which options would further be developed and studied. These values are subject to change as the option are further developed.



OPM Update



OPM Update

R	2		Concord - Carlisl Proposed Proje			ol	KVA
ID	% Complete	0	Task Name	Duration	Start	Finish	2011 o e Jan e MarApr a Jun Jul u e Oct o
48	0%		Building systems descriptions (Struct/MEP/Comm/Sustainable design)	24 days	Thu 6/23/11	Tue 7/26/11	
19	0%		Preliminary summary of ineligible spaces	24 days	Thu 6/23/11	Tue 7/26/11	
50	0%		Outline Specs	24 days	Thu 6/23/11	Tue 7/26/11	
51	0%		MA-CHPS Score card	24 days	Thu 6/23/11	Tue 7/26/11	
2	0%		FFE spec and estimate	24 days	Thu 6/23/11	Tue 7/26/11	
3	0%		Construction Estimate(s)	15 days	Wed 7/27/11	Tue 8/16/11	_
64	0%		Budget	10 days	Fri 8/5/11	Thu 8/18/11	
55	0%	П	Project budget	9 days	Fri 8/5/11	Wed 8/17/11	
56	0%	П	Summary of ineligible costs	5 days	Mon 8/8/11	Fri 8/12/11	
57	0%	П	Project cash flow	1 day	Wed 8/17/11	Wed 8/17/11	I
58	0%		MSBA 3011 form	2 days	Wed 8/17/11	Thu 8/18/11	<u> </u>
59	0%		Submit Schematic Design to the MSBA (for Sept BOD vote)	1 day	Fri 8/19/11	Fri 8/19/11	♦ 8/19
60	0%		Establish a Project Scope and Budget Agreement (MOD 5)	10 days	Mon 9/5/11	Fri 9/16/11	*
61	0%	ш	MSBA BOD Mtg - Sept 28th - Approves Concord-Carlisle PFA	1 day	Wed 9/28/11	Wed 9/28/11	♦ 9/28
62	0%		CCHSC markets project to Concord and Carlisle	30 days	Thu 9/29/11	Wed 11/9/11	<u> </u>
63	0%	TI.	CCHSC votes to accept PFA with the MSBA	1 day	Thu 11/10/11	Thu 11/10/11	F
64	0%		School Committee requests BOS to authorize debt exclusion	1 day	Tue 10/4/11	Tue 10/4/11	I
65	0%		November STM	1 day	Mon 11/7/11	Mon 11/7/11	*
36	0%	П	Execute PBSA	1 day	Fri 11/11/11	Fri 11/11/11	I
67	0%		Execute PFA (120 days from Board approval)	15 days	Mon 11/21/11	Fri 12/9/11	

CCHS Feasibility Study Work Plan

Groundwork	 Prepare contract Obtain and review all available/ pertinent documents Prepare schedule and work plan 	 Review existing conditions information Attend Site Based Committee Meeting Conduct User Group meetings and Prepare Space Summary
Meeting # 1	Goals, Values and Space Summary	
3/09/11	Objectives Review schedule and process Review goals, values Review proposed space summary	Follow-up Site walk thru with Engineers and Facilities Manager Submit draft space summary to MSBA for initial review Meet with MSBA for kickoff meeting Prepare Preliminary Alternative concepts
Meeting # 2	Vision, Space Summary and Preliminary Al	ternatives Concepts
3/23/11	Objectives Review Educational Vision, goals and values Review Preliminary Alternative Concepts Approve Initial Space Summary and PDP	 Follow-up Complete Preliminary Design Program Submittal for MSBA Meet with MSBA Develop Preliminary Alternatives
Meeting # 3	Sustainability Goals	
4/06/11	Objectives o Discuss sustainability goals and net zero options with team	Follow-up o Develop Preliminary Evaluation of Proposed Alternatives
Meeting # 4	Preliminary Evaluation of Proposed Alterna	atives
4/13/11	Objectives o Review Preliminary Evaluation of Proposed Alternatives	Follow-up Submit Preliminary Alternatives to MSBA for initial review Meet with MSBA Develop Final Evaluation of Selected Alternatives
Meeting # 5	Finalize Preliminary Alternatives	
5/04/11	Objectives o Review and Approve Preliminary Alternative(s)	Follow-up o Prepare Final Evaluation of Alternatives
Meeting # 6	Final Evaluation of Alternatives	
5/18/11	Objectives Review Final Evaluation of Alternatives Confirm Preferred Solution	Follow-up o Prepare Preferred Schematic Report
Meeting # 7	Preferred Schematic Report	
5/25/11	Objectives	Follow-up

o Review and Approve Preferred Schematic Report

o Submit Preferred Schematic Report to MSBA

o MSBA Facilities Assessment Subcommittee and BOD Vote

GOALS: Process

- Partnering with the MSBA, proactively manage the process with foresight and insight in an integrated manner.
- Communicate clearly, convincingly, strategically and sensitively regarding the issues and challenges intrinsic to building momentum for this project at this time
- Model and reflect our Communities' values with a design that fosters civic pride and environmental stewardship, and garners social, financial and political support
- **Explore financial options** with public/private partnerships and develop innovative ways to generate project funding and sustainable income

GOALS: Project

- Develop a project which is fiscally, academically, environmentally and socially responsible
- Design a facility which is flexible, adaptable, affordable and achievable
- Create a facility that is fully accessible, highly functional, cost effective, high performing, durable, and easy to maintain
- Plan for a fully integrated campus that promotes 21st century learning, educational excellence, high performance and shared intergenerational community and recreational use
- Actively engage our communities in this ongoing and exciting opportunity for teaching and learning
- Holistically integrate all campus elements into a practical and inspiring new and transformed CCHS

As approved by CCHS SBC on 3/09/11

GOALS: Product

- Create a campus which is safe and secure
- Provide state-of-the-art facilities with the full and appropriate array of formal and informal learning, gathering, and performance spaces
- Provide state-of-the-art building systems in an environment with an abundance of natural light, clean healthy air, and practical, sustainable and high performance design strategies
- Integrate and maximize the current and future use of effective, cuttingedge technologies
- Develop intuitively clear, logical and efficient organizational and circulation patterns
- Build an inspiring and engaging center for "24/7" community use
- Minimize the impact of the design and construction on the students, teachers, parents, neighbors and the greater community

As approved by CCHS SBC on 3/09/11

Program Summary


OMR Architects, Inc.

Concord-Carlisle High School Space Summary Comparison

Date: 3/21/2011

Description	Existing Program	Proposed Program - 2011	MSBA Guidelines - 2010	Delta:
		1225 Enrollment	1225 Enrollment	Prop - MSBA
CORE ACADEMIC SPACES	56,126	62,595	58,690	3,905
SPED	7,145	5,970	13,090	(7,120)
ART & MUSIC (Visual and Perf. Arts)	11,779	13,625	8,200	5,425
VOCATIONS & TECHNOLOGY	8,035	8,350	12,800	(4,450)
HEALTH AND PHYSICAL EDUCATION	35,025	36,610	23,060	13,550
MEDIA-LIBRARY (Learning Commons)	13,480	8,600	7,556	1,044
AUDITORIUM / DRAMA	9,667	10,400	10,400	0
DINING & FOOD SERVICE	13,068	10,262	10,262	(0)
MEDICAL / NURSE	690	1,110	1,110	0
ADM. & GUIDANCE (Student Support)	8,462	6,755	4,979	1,776
CUSTODIAL & MAINTENANCE	2,779	2,544	2,544	0
SUB-TOTAL				
Net Area	166,256	166,821	152,692	14,129
OTHER	4,134	3,690	0	3,690
GRAND TOTAL				
Net Area	170,390	170,511	152,692	17,819
Net:Gross Ratio (Net Area / Gross Area)	1.37	1.45	1.45	1.45
Gross Area	233,800	247,241	221,725	25,516

Space Adjacency Diagram



Meeting #3 Summary




Meeting #4 Summary




Option 4R Major Addition / Major Renovation




Major Addition / Minor Renovation



Option 9/10 **New Building**



Option 11 **New Building**



Option 12 New Building

Integrated Design Team Highlights

- Study active vs. passive strategies
- Optimize daylighting and views throughout
- Include north facing classrooms
- Integrate clustering with vertical ventilation / light shafts
- Integrate tight building envelope
- Consider integrated hybrid approach for building systems
- Balance sustainability ideas with maintenance and operations
- Use quantifiable data to determine feasibility / value
- Consider solar wall system
- Consider PV array at grade
- Use LED lighting at exterior and as an alternate on the interior
- Sustainable subcommittee to oversee 3rd party PV financing / CMLP



Option 6R1 Major Renovation Major Addition



Option 12R New Building (1 Step)

Revised Space Summary: To be Approved by SBC

247,241 G.S.F. further reduced to 242,275 G.S.F.

Art Gallery moved to Other.

300 NSF of **Art Storage moved** to Gross.

Health Classroom added in Core Academics.

Gymnasiums reduced by 1,000 NSF.

PE Alternative- Multipurpose space reduced to 2175 NSF.


Officials/ coaches locker rooms deleted.

Trainer's room reduced to 500 NSF.

Visiting Team Room deleted.

CCHS Team Rooms reduced to 3 rooms, 2 at 500 NSF and 1 at 675 NSF.


Option 6R1: Ground Floor Plan



Option 6R1: 2nd Floor Plan




Option 6R1: 3rd Floor Plan




Option 6R1: Ground Floor Plan




Option 6R1: Lower Floor Plan



Option 6R1: Conceptual Sections




Section at Entry



Section at Gymnasium

Option 6R1: View from North




Option 6R1: View from East




Option 6R1: View from South




Option 6R1: View from West




Option 12R: Ground Floor Plan




Option 12R: Lower Floor Plan




Option 12R: Ground Floor Plan




Option 12R: 2nd Floor Plan




Option 12R: 3rd Floor Plan



Option 12R: Conceptual Sections




Section at Ground & Lower Entries




Section at Gymnasium


Option 12R: View from North




Option 12R: View from East




Option 12R: View from South



Option 12R: View from West



Summary




Option 6R1 Major Renovation Major Addition



Option 12R New Building (1 Step)

Evaluation Matrices



Evaluation Matrices

valuation Criteria Matrix		r-ag	
		A CONTRACTOR OF THE PARTY OF TH	TRANS
	A TELEPHONOMENT TO		
	The state of the state of		HO PRO
	E 20 0 0 0 0 0 0 0		000
	1		
Legend		WIN -	
Moderate / Neutral	Addition & Ren	ovation Options	All New Construction Opti
1 Proc	4	6R1	12R
2 Setisfactory	Major Renovation	Minor Renovation	111111111111111111111111111111111111111
3 Advantagroup	Major Additions	Major Additions	New Building
4 Highly Advantageous	(Keep 'A', 'H', and Cafe.)	(Keep 'A' and Cafe.)	(1 Step)
4 Prignit revenuellance			
DUBATION	46 months	44 Months	32 Months
COST	98.3 Million	97.7 Million	91.1 Million
Cost Effective/ Value			
Educational Program Needs			
-			
Building Transformation			
Expandability			
Project and Product Goals :			
COMMUNITY VALUES: Model and reflect our Communities' values with a			
design that fosters civic pride and environmental stewardship, and garners social,			
financial and political support			
- RESPONSIBLE DESIGN: Develop a project which is fiscally, academically,			
environmentally and socially responsible			
 FLEXIBLE/ ADAPTABLE: Design a facility which is flexible, adaptable, affordable 			
and achievable			
 MAINTAINABILITY: Create a facility that is fully accessible, highly functional, cost effective, high performing, durable, and easy to maintain 			
- COMMUNITY USE: Plan for a fully integrated campus that promotes 21st			
century learning, educational excellence, high performance and shared			
intergenerational community and recreational use			
- COMMUNITY SUPPORT: Actively engage our communities in this ongoing and			
exciting opportunity for teaching and learning			
 CAMPUS INTEGRATION: Holistically integrate all campus elements into a practical and inspiring new and transformed CCHS 			
practical and inspiring new and transformed CCPS			
SECURE CAMPUS: Create a campus which is safe and secure			
- SECURE CAMPOS: Create a campus which is sale and secure			
• 21ST CENTURY PROGRAMMATIC SPACE: Provide state-of-the-art facilities with			
the full and appropriate array of formal and informal learning, gathering, and			
performance spaces			
 SUSTAINABILITY: Provide state-of-the-art building systems in an environment 			
with an abundance of natural light, clean healthy air, and practical, sustainable and high performance design strategies			
 EFFICIENT/LOGICAL ORGANIZATION: Develop intuitively clear, logical and efficient organizational and circulation patterns 			
- 24/7 Community Use: Build an inspiring and engaging center for "24/7"			
community use			
 MINIMAL PHASING DISRUPTION: Minimize the impact of the design and 			
construction on the students, teachers, parents, neighbors and the greater community			
- PROACTIVELY PROCESS: Partnering with MSBA to proactively manage the			
 PROCEIVELY PROCESS: Partnering with MSBA to proactively manage the process with foresight and insight in an integrated manner 		0	
and the state of t	, , , , , , , , , , , , , , , , , , ,		
<u>COMMUNICATION:</u> Communicate clearly, convincingly, strategically and			
sensitively regarding the issues and challenges intrinsic to building momentum for		0	0
this project at this time	1	_	
 FUND RAISING: Explore financial options with public/private partnerships and 			
develop innovative ways to generate project funding and sustainable income	0	0	0
 TECHNOLGY: Integrate and maximize the current and future use of effective, 			
cutting-edge technologies	0	0	0

Next Steps

May 11th MSBA Meeting

SBC Meeting #6, May 18, 2011

- Review Final Evaluation of Alternatives
- Confirm Preferred Solution